BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of the Work: Excavation for Temporary immersion Tank for Lord Ganesh idoles in ward no. 10 Doddabommasandra Vidyaranyapura sub division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	42.00	Earth work in surface excavation in **hard soil** for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed etc complete as per specifications and directions of engineer in charge of the work	Cum	201.40	
2	214.50	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, **in Hard soil** not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	259.70	
	214.50	Above 1.5 Mtrs Depth Add 25% Extra		247.78	
3	820.00	Code 0516 - Providing Plastic Sheet etc complete as per specifications and directions of engineer in charge of the work	Sqm	5.00	
4	165.00	Supply of water Through water Tank for filling Tank etc complete as per specifications and directions of engineer in charge of the work	Each	350.00	
5	12.50	Providing Stone dust to approach road and near immersion tank for levelling and to protect not to sliping Sl No. 50 Code 400 metal Component etc complete as per specifications and directions of engineer in charge of the work	Cum	180.00	
6	66.00	Hire charge of pumping water 3.5 KL/hr capacity Pump etc complete as per specifications and directions of engineer in charge of the work	Hrs	35.00	
7	165	Engaging unskilled heavy Mazdoor laboru for Guarding and for helping the public to immersion tank Ganesh Idols and to safe guard the public during the pooja Time etc complete as per specifications and directions of engineer in charge of the work	Days	183.24	
8	3355.00	Hire Charges for Two Tier Barricading with casurens poles at 2.50mtrs C/C vertically and 0.50 mtrs C/C Horizontaly with Necessary earth work and labour etc complete as per specifications and directions of engineer in charge of the work	Rft	17.00	
9	13200.00	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 40ft x 30ft = 1200 sqft) etc complete as per specifications and directions of engineer in charge of the work	Sft	3.00	

T.S. (15% C.P.)

10	550.00	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft) etc complete as per specifications and directions of engineer in charge of the work	Rft	17.00	
11	550.00	Hire Charge for Armless Plastic Chairs etc complete as per specifications and directions of engineer in charge of the work	Nos	4.00	
12	110	Hire Charge for Wooden Table of Size 6ft x 2ft etc complete as per specifications and directions of engineer in charge of the work	Nos	40.00	
13	2200.00	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathe daluminium wire etc complete as per specifications and directions of engineer in charge of the work	Mtrs	9.00	
14	88	Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges etc complete as per specifications and directions of engineer in charge of the work	Hrs	562.00	
15	154.00	Hire chargesfor Flood lighting arrangements for the stage and existing immersion Tank during night time etc complete as per specifications and directions of engineer in charge of the work	Nos	285.00	
16	6	Hire charges compoment name 1087 Crane charges etc complete as per specifications and directions of engineer in charge of the work	Day	3200.00	
17	429.00	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour etc complete as per specifications and directions of engineer in charge of the work	Cum	71.28	

Signture of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಕರಡು ಟೆಂಡರ್ ಪಡ್ಯೂಲ್‌ನ್ನು
ಶಿದ್ಧುಪಡಿಗಳ ಸಂಖ್ಯೆ.....(N)2
ಶಿದ್ಧುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ